


AD-A117 972

CONSTRUCTION ENGINEERING RESEARCH LAB (ARMY) CHAMPAIGN IL F/G 9/2  
CAEDS--COMPUTER-AIDED ENGINEERING AND ARCHITECTURAL DESIGN SYST--ETC(U)  
1982 J H SPOONAMORE

UNCLASSIFIED

NL

[m]  
[m]



END  
DATE  
FILMED  
69-82  
DTIC

construction  
engineering  
research  
laboratory



United States Army  
Corps of Engineers  
... Serving the Army  
... Serving the Nation

TECHNICAL MANUSCRIPT P-133  
August 1982

12

CAEADS—COMPUTER-AIDED ENGINEERING  
AND ARCHITECTURAL DESIGN SYSTEM

by  
Janet H. Spoonamore

AUG 30 1982



DTIC FILE COPY

82 00 013  
Approved for public release; distribution unlimited.

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

***DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR***

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER 7M CERL- <del>7M</del> -P-133	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) CAEADS -- COMPUTER-AIDED ENGINEERING AND ARCHITECTURAL DESIGN SYSTEM		5. TYPE OF REPORT & PERIOD COVERED FINAL
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Janet H. Spoonamore		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. BOX 4005, CHAMPAING, IL 61820		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 4A762731AT41-A-020
11. CONTROLLING OFFICE NAME AND ADDRESS		12. REPORT DATE August 1982
		13. NUMBER OF PAGES 22
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Copies are obtainable from the National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) CAEADS Computer-Aided Engineering and Architectural Design System military facilities computer-aided design		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  CAEADS, an automated integrated system to support the design of mili- tary facilities, is being developed by the U.S. Army Construction Engineering Research Laboratory through the Corps of Engineers' RDTE Pro- gram. When completed, the entire CAEADS system will support the design process starting at the initiation of a requirement for a facility, and continue through to the design (preliminary and final) and the production		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

7

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

BLOCK 20. (Cont'd)

of working drawings, specifications and cost estimates. Presently, Concept CAEADS integrates tools for use in preliminary design. Concept CAEADS has been extensively tested by architects and engineers on the design of 200 projects in the FY84 Military Construction Army Program. During this test, Concept CAEADS was used to organize project requirements, lay out facility floor plans, evaluate designs for functionality and energy usage, do preliminary cost estimates, and produce concept-level drawings. By using Concept CAEADS' tools and exploiting repetition in the design workload, costs for concept design were reduced substantially. These savings are attributed to adaptation of standard designs in an integrated environment, where design changes are made simply and quickly.

This paper presents the findings of the recent Concept CAEADS test and describes future CAEADS development -- Predesign and Final Design CAEADS.

2  
UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)


# FOREWORD

This paper was presented at the 1982 Army Science Conference, held at the U.S. Military Academy, West Point, New York, 15-18 June 1982. The CAEADS work was performed for the Directorate of Military Programs, Office of the Chief of Engineers, under Project 4A762731AT41, "Military Facilities Engineering Technology"; Task A, "Facility Planning and Design"; Work Unit 020, "Computer-Aided Engineering and Architectural Design System." Mr. Vincent Gottschalk, DAEN-MPE, was the OCE Technical Monitor.

The work was performed by the CAEADS Team, Facilities Systems (FS) Division of the U.S. Army Construction Engineering Research Laboratory (CERL). Mr. Ed Lotz is Chief of CERL-FS, and Janet Spoonamore is Team Leader for the CAEADS team.

COL Louis J. Circeo is Commander and Director of CERL, and Dr. L. R. Shaffer is Technical Director.

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution _____	
Availability Codes	
Availability Statement	
Special	
A	



CAEADS — COMPUTER-AIDED ENGINEERING AND ARCHITECTURAL DESIGN SYSTEM (U)

JANET H. SPOONAMORE\*  
U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY  
CHAMPAIGN, IL 61820

The U.S. Army Corps of Engineers Construction Engineering Research Laboratory is developing the Computer-Aided Engineering and Architectural Design System (CAEADS) to support the design of military facilities. CAEADS' support will start with initial requirements for a facility, and continue through concept and final design and the production of construction drawings, specifications and cost estimates. The CAEADS system will be integrated based on a central source of design information used by all the disciplines in the design process: users, project planners, architects, engineers, specification writers, and cost estimators and drafters.

In October of 1981, the integration of the concept design tools of the CAEADS system was completed and a test initiated involving 200 projects in the Military Construction Army (MCA) FY84 program. This integrated system, called Concept CAEADS, is used to support preliminary design, from project requirements through to the 25 percent design level. Concept CAEADS provides tools for project information retrieval, facility layout, functional evaluation, energy evaluation, cost estimating and production of drawings. During the period 1 October 81 to 1 February 82, one architectural engineering firm tested and used Concept CAEADS to design to 25 percent these 200 MCA projects. The findings of the test suggest that substantial design cost reductions will be realized. The purpose of this paper is to report on the Concept CAEADS test objectives and findings and describe the development of a further integration of design tools -- Predesign and Final Design CAEADS.

Background

The Corps of Engineers is the largest construction industry in the world. Each year, the Corps' MCA program includes several hundred projects consisting of some 50 facility types in various stages of planning, design or construction. For several years, total MCA construction has

grown both in volume and technical complexity. Keeping construction costs low given increasing demands for energy and concerns for safety, accessibility, and efficiency in an environment of rising construction labor and material costs is a great challenge. This challenge means the Corps must design the best possible facilities, reuse these "best" designs, and manage construction programs to optimize on repetition. Further quality can be gained and time saved by using automated tools to support design layout, analysis and drawing production on repetitive, "similar" projects. The CAEADS system is being developed to meet this objective; i.e., to reduce design costs and increase the quality of design.

#### Computer-Aided Design Technology

Computer-aided design (CAD) tools for engineering and construction have been adapted mainly from manufacturing and business applications; software for accounting, specification production and drafting are presently available. These individual tools now are being linked using a geometric description of the design, i.e., a central source of data. Computer graphics and geometry are used like balsa-wood models, but can do much more -- functional analysis, quantity take-offs, statistical analysis, and heating and cooling analysis, etc. For example, using the geometric operations, interferences between the layout of structural elements and heating, ventilating, and air conditioning (HVAC) ducts can be detected. According to Engineering News-Record (December 1981), CAD may bring the most profound changes in standard procedures the design profession has ever seen (1).

CAEADS focuses on assembling hardware and software tools affordable by and compatible with the architect/engineer (A/E) organizations that will be using the system on Corps projects (2).

The benefits an integrated system such as CAEADS will offer the Corps are far-reaching. The MCA design process can be shortened and strengthened using CAEADS. CAEADS can increase productivity, and help the Corps exploit the opportunity of repetition of similar designs. (Repetition is especially amenable to automation.) CAEADS allows more analyses to be performed to detect design errors such as interferences in construction, poor layout, etc. CAEADS also gives the Corps an efficient way to make continual evaluations to trade off expected construction costs and operating energy costs. CAEADS will produce benefits and savings in the design, construction and operation and maintenance of facilities.



### Concept CAEADS Description

CAEADS has only recently become available as an integrated system. Over the past several years, CERL and other Corps organizations have developed specific, stand-alone application tools under the CAEADS umbrella. The systems include the Design Information System (DIS), developed by the Office of the Chief of Engineers; the Automated Budget Estimating System (ABES) and the Computer-Aided Cost Estimating System (CACES), developed by the U.S. Army Engineer Division, Middle East (Rear); and the CERL-developed DD 1391 Processor, the Systematic Evaluation of Architectural Criteria (SEARCH), the Computer-Aided Facility Layout System (SKETCH), the Building Loads Analysis and Thermodynamics (BLAST) System, and the Computer-Aided Specification Preparation System (EDITSPEC).

Concept CAEADS integrates automated tools for use at the early stages of design, primarily the functional layout and analysis phases. Figure 1, "CAEADS Concept Design," depicts these tools. The system helps designers organize project information, lay out design alternatives, analyze for compliance to functional requirements, evaluate energy consumption and costs, estimate direct project costs and produce scaled drawings. Concept CAEADS provides a 3-dimensional data base from which final design can be initiated.

In the concept design phase, the designer will generate one or more conceptual design solutions. Each alternative is evaluated and reviewed to assure it complies with the facility users' needs and other design criteria.

The Concept CAEADS design process includes the following steps:

1. The DIS module is used to review the MCA project design information in a given fiscal year and identify projects that can use "as-designed" standards. Project information is maintained at a summary level in the DD 1391 Processor data bases.
2. The SKETCH module is used to develop custom layouts or to modify standards. The system provides layout tools for rooms, walls, doors, windows, ceilings, floors, furniture and equipment, thermal zones and associated construction materials.
3. The SEARCH evaluation modules are used to check alternatives to assure they comply with a project's functional requirements. These include area, walking distance, acoustic separation, visual control and handicap accessibility codes.




Figure 1. CAEADS Concept Design

4. The BLAST module analyzes alternatives for energy consumption and costs (3). BLAST predicts consumption based on simulated geographic weather and building operations.

5. The ABES/CACES modules prepare preliminary cost estimates for each alternative. A data base library of construction and unit costs is maintained in the system.

Designers access Concept CAEADS using low-cost graphics workstation terminals. Layouts are entered using the terminal thumbwell movements; displays are shown on the terminal screen. Hardcopy plots of final layouts can be produced. The functional evaluation, energy usage and cost estimate reports also are produced by the system at this workstation.

Concept CAEADS currently operates on timesharing services at the University of Michigan, Michigan State University, and the Mid-East Rear Division.

#### Concept CAEADS Test Objectives

The test of the Concept CAEADS system had three objectives:

1. Determine the usability of a system like CAEADS.
2. Determine the costs and benefits of applying CAEADS to a design workload.
3. Determine the design workload distribution which would ensure the highest payoff using CAEADS.

#### *Usability*

A system like CAEADS may or may not be accepted and properly used by practitioners, although it closely supports normal design practice. Human factor issues are very important. The use of automation in architectural/engineering practice historically has been very low compared to other professions. But with the initiation of computer-aided drafting in the A/E community, it seems likely that a CAD system will be accepted and used. Only the essential differences between automated drafting and automated design tools need to be explored. Table 1, "Summary of Concept CAEADS Versus Automated Drafting," shows the differences between drafting tools and design tools. The Concept CAEADS test helped determine whether these design tools could be incorporated into practice, in much the same way as drafting tools have been.

Table 1

Summary of Concept CAEADS Versus Automated Drafting

Automated Drafting (Typical turn-key system)

- Drawing tools
  - Definition of levels/pages
  - Definition of repeating group of elements
  - Layout of elements
    - Annotation
    - Points
    - Lines
    - Polygons
    - Polyhedron
    - Group of elements
  - Modification of above (changes or deletions)
  - Line-weighting, cross-hatching, fill, font selection, paragraphing, formatting.
  - Dimensioning notation (semi-automatic)
  - Accuracy controls (snapping to grids, points)
- Plotting tools
  - Selection of scale, region to be plotted.
- Association of elements to nongraphic data

Concept CAEADS

- Design tools
  - Definition of project criteria
    - Room areas/proximities/visual control
    - Handicap criteria
    - Location
  - Layout of alternative plan elements
    - Floors, ceilings, roofs, doors, windows, equipment/furniture or groups of these
    - Selection of materials for above
    - Automatic generation of room polygons
    - Definition of room names and HVAC zones (plants, air handling)
    - Stretching/shrinking capability
    - Accuracy controls (snapping to grids, points, angles)
- Analysis tools
  - Calculation of layout against project criteria
  - Calculation of quantities and direct costs
  - Calculation of heating/cooling BTUs
- Plotting tools
  - Automatic generation of scaled drawings
- Translation of elements into graphic data for further lineweighting, dimensioning, annotation, fill and font selection.

The test showed that Concept CAEADS could be applied directly to design practice. Training on the system (i.e., learning the system functions and applying them to the design efforts) went well throughout the course of the test. Only simple problems occurred during the test, including computer "downtime," causing work stoppage; minor system errors; and user difficulties in not understanding how the system operated. During the first several weeks of the test, the A/E staff quickly adapted to the new functions offered by Concept CAEADS.

Midway through the test, the A/E staff was asked to fill out a questionnaire about the system's utility and ease of use. The questionnaire also asked the A/Es to compare Concept CAEADS to manual and automated drafting approaches, and to suggest improvements. The users who actually operated the system included three architects and one mechanical engineer. These persons used the SKETCH system to do floor plan layouts and to specify HVAC zones and building materials. They also ran off the SEARCH drawings, BLAST energy profiles and ABES/CACES cost estimates.

The questionnaire results indicated the staff felt the system was useful for adapting past project or definitive layouts to meet established criteria. They also felt the system's strong evaluation features were useful. Their negative reactions focused on several of the user protocol procedures, which they felt slowed their performance. Based on their recommendations, many of these procedures already have been enhanced and are now much easier to perform.

#### *Costs/Benefits*

The use of Concept CAEADS on 200 MCA project designs produced considerable savings over current practice. It should be noted that savings were realized not only from use of the system, but also from the consolidated design workload on which the system was used. The costs for the 200 projects included design personnel costs, computer timesharing services costs, equipment rental costs and software maintenance/training personnel costs. These costs are shown in Table 2, "Concept CAEADS Test Costs." Costs using current methods of design practice were derived from typical project design costs incurred in the past. An average cost for 25 percent project design (on similar design workloads) was approximately \$16,000 using current manual methods. The number of completed projects in the test workload was 113 out of the original 205 started. Ninety-two projects were cancelled during the progress of the work. On the average, these 92 projects were completed to about 10 percent. The costs to perform the design using current practice are shown in Table 3, "Current Practice Costs."

Table 2  
Concept CAEADS Test Costs

<u>Costs</u>	
Design personnel	\$200,000
Automated data processing timesharing	100,000
Equipment rental	16,000
Software maintenance/training	<u>40,000</u>
	\$356,000

Table 3  
Current Practice Costs

<u>Projects</u>	<u>Cost/Project</u>	<u>Total</u>
113	\$16,000	\$1,808,000
92	6,400	<u>588,800</u>
	TOTAL	\$2,396,800

Table 3 shows that more than \$2 million in cost savings were realized using Concept CAEADS.

#### *Design Workload Distribution*

As mentioned earlier, the users of the Concept CAEADS system felt the system was amenable to adapting designs based on definitive or past project layouts, and that design workload distribution was an important ingredient in realizing high-payoffs from automation. Table 4, "Project Distribution," shows the range and scope of facilities designed. This workload included new construction of building projects.

Table 4  
Project Distribution

<u>Category Code</u>	<u>Number of Projects</u>	<u>Approximate Square Feet</u>
141 Field operations	5	9,000
	2	13,000
	2	18,500
	1	4,000
	1	4,000
171 Headquarters	6	12,000
	2	17,000
	1	25,000
	1	28,000
	1	35,000
	6	Ranges (25,000 - 63,000) Average (41,500)
214 Vehicle maintenance	9	4,000
	2	14,000
	2	19,000
	1	26,000
	1	29,000
	2	33,000
	1	49,000
	2	225,000
	1	12,000
219 Maintenance -- FE	1	12,000
	1	28,000
	1	34,000
	2	3,500
610 Administration	1	35,000
	1	85,000
	3	8,000
722 Dining	3	12,000
	1	16,000
	1	48,000
	1	

Table 4 (Cont'd)

<u>Category Code</u>	<u>Number of Projects</u>	<u>Approximate Square Feet</u>
723 Company administration	4	5,000
	1	14,000
	1	19,000
	2	24,000
	1	29,000
	1	34,000
	2	43,000
	1	71,000
	1	78,000
724 Officers housing	1	52,000
730 Fire stations	2	5,000
	2	6,000
740 Morale support	19	Ranges (3,000-62,000)
• Child care		Average (30,000)
• Education/library		
• Physical fitness centers		
• Recreation centers		

As expected, there was considerable variation in layout time required to modify drawings versus original custom design layout. The online usage data collected during the test revealed an average of 12 hours per layout (minimum 0, maximum 24 hours) with a standard deviation of 15. Having access to a central library of design layouts and tools to modify these floor plans for specific project requirements and location gave designers the opportunity to "reuse" designs. This approach resulted in the lowest possible design costs at no sacrifice to quality.

#### *Further Developments*

This extensive test answered several questions. CAEADS easily can be incorporated into design practice -- it is usable. It is cost effective and the repetitive workload of the MCA program is especially amenable to high-cost avoidance.

Two main questions arose during the test which must be answered. First, project design information is sometimes lacking at the start of the design process. How can this project requirement information best be collected and organized for design initiation? Much of this data is generated by the Army installation user, and ultimately is documented in the Project Development Brochure (PDB). Proposed construction projects must



be approved and contained in the Installation Master Plans (including the approved site). A new module of CAEADS -- Predesign CAEADS -- will be developed to integrate the tools to support the development of project requirements (functional and technical requirements), the analysis of supporting utility requirements compared to capacity and environmental and economic impact analysis. Predesign CAEADS will be used primarily by Corps district offices supporting installations preparing MCA project information.

A second question posed during the test regards the transition of the concept design into final design (usually performed under A/E services). Given project designs completed to concept level, a means must be provided to transfer these designs to the many A/E firms which ultimately will provide working drawings, specifications and detailed design analysis. The system which will provide this transition is called Final Design CAEADS. This system will integrate several of the stand-alone systems previously mentioned (BLAST, CACES, EDITSPEC) and a sophisticated 3-dimensional modeling data base for representing the design. The 3-dimensional data base provides a central source of data from which specifications can be prepared, quantities calculated for detailed cost estimates and analysis performed (structural, electrical and mechanical). The system ARCH:MODEL, developed by the University of Michigan Architectural Research Laboratory, will provide the data base handling and geometric modeling tools needed for fully representing and retrieving the elements of design, i.e., doors, windows, ceiling, roof, foundations, structure, mechanical and mechanical/electrical conduit (4). ARCH:MODEL's geometric operations on 3-dimensional polyhedra allow for checking interferences in building system layout. Presently, an interface has been developed to transfer concept-level floor plans into a 3-dimensional model of the facility design. Figures 2 through 7 depict the development of a design using ARCH:MODEL.

### Conclusions

The recent test of Concept CAEADS has provided a unique opportunity to evaluate the impacts of CAD on a wide range of project design workloads. The findings of the test show the usability of CAD in design practice and the benefits of CAD applied on a consolidated concept design workload. Development of the Predesign and Final Design modules of CAEADS will be performed over the next 5 years.

### References

- (1) Engineering-News Record, December 3, 1981, "Computer-Aided Everything," pp 34-61.
- (2) "Computer-Aided Engineering and Architectural Design System (CAEADS), Volume I: Summary," U.S. Army Construction Engineering Research Laboratory, Champaign, IL, CERL-TR-P-97, Jan 1979.
- (3) "The Building Loads Analysis System Thermodynamics (BLAST) Program, Version 2.0: Users Manual, Volume I," U.S. Army Construction Engineering Research Laboratory, Champaign, IL, CERL-TR-E-153, June 1979.
- (4) "ARCH:MODEL, Version 1-2, Geometric Modeling Relational Database System," Architectural Research Laboratory, College of Agriculture and Urban Planning, University of Michigan, Ann Arbor, Michigan, July 1981.




Figure 2. Transfer of layout to 3-dimensional model (includes ceramic floor tiles for passive solar design).




Figure 3. Extrusion of walls into 3-dimensional polyhedron.




Figure 4. Roof section laid out in SKETCH and extruded. Louver windows and solar collection panels are built in 2-dimensions and placed on roof.




Figure 5. Roof is placed on building and berms are placed on north, west and east sides.




Figure 6. Footings, foundations, columns, and girders are sketched and extruded. Presently, sizing and layout are calculated outside CAEADS. Eventually, an automated interface will be provided.




Figure 7. Conflicts in placement of components can be detected, e.g., the girder and roof.

CERL DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: DAEN-AS1-1 (2)  
ATTN: DAEN-CCP  
ATTN: DAEN-CW  
ATTN: DAEN-CWE  
ATTN: DAEN-CWM-R  
ATTN: DAEN-CWO  
ATTN: DAEN-CWP  
ATTN: DAEN-MP  
ATTN: DAEN-MPC  
ATTN: DAEN-MPE  
ATTN: DAEN-MPO  
ATTN: DAEN-MPR-A  
ATTN: DAEN-RD  
ATTN: DAEN-RDC  
ATTN: DAEN-RDM  
ATTN: DAEN-RM  
ATTN: DAEN-ZC  
ATTN: DAEN-ZCE  
ATTN: DAEN-ZCI  
ATTN: DAEN-ZCM

FESA, ATTN: Library 22060

FESA, ATTN: DET III 79906

US Army Engineer Districts  
ATTN: Library  
Alaska 99501  
Al Batin 09616  
Albuquerque 87103  
Baltimore 21203  
Buffalo 14207  
Charleston 29402  
Chicago 60604  
Detroit 48231  
Far East 96301  
Fort Worth 76102  
Galveston 77550  
Huntington 25721  
Jacksonville 32232  
Japan 96343  
Kansas City 64106  
Little Rock 72203  
Los Angeles 90053  
Louisville 40201  
Memphis 38101  
Mobile 36628  
Nashville 37202  
New Orleans 70160  
New York 10007  
Norfolk 23510  
Omaha 68102  
Philadelphia 19106  
Pittsburgh 15222  
Portland 97208  
Riyadh 09038  
Rock Island 61201  
Sacramento 95814  
San Francisco 94105  
Savannah 31402  
Seattle 98124  
St. Louis 63101  
St. Paul 55101  
Tulsa 74102  
Wicksburg 39180  
Walla Walla 99362  
Wilmington 28401

US Army Engineer Divisions  
ATTN: Library  
Europe 09707  
Huntsville 35807  
Lower Mississippi Valley 39180  
Middle East 09038  
Middle East (Rear) 22601  
Missouri River 68101  
New England 02154  
North Atlantic 10007  
North Central 60605  
North Pacific 97208  
Ohio River 45201  
Pacific Ocean 96858  
South Atlantic 30303  
South Pacific 94111  
Southwestern 75202

US Army Europe  
HQ, 1st Army Training Command 09114  
ATTN: AETG-DEH (5)  
HQ, 1st Army ODCS/Engr. 09403  
ATTN: AEAEN-EH (4)  
V. Corps 09079  
ATTN: AETVDEH (5)  
VII. Corps 09154  
ATTN: AETSDEN (5)  
21st Support Command 09325  
ATTN: AEREM (5)  
Berlin 09742  
ATTN: AERA-EN (2)  
Southern European Task Force 09168  
ATTN: AESK-LMG (3)  
Installation Support Activity 09403  
ATTN: AFURS-RP

8th USA, Korea  
ATTN: EAFE (8) 96301  
ATTN: EAFE-Y 96358  
ATTN: EAFE-ID 96224  
ATTN: EAFE-AM 96208

8th USA, Korea  
ATTN: EAFE-N 96271  
ATTN: EAFE-P 96259  
ATTN: EAFE-T 96212  
ROE/US Combined Forces Command 96301  
ATTN: EUSA-HHC-CFC/Engr

USA Japan (USARJ)  
Ch, FE Div, AJEN-FE 96343  
Fac Engr (Monsu) 96343  
Fac Engr (Okinawa) 96331

Rocky Mt. Arsenal, SAREM-IS 80022  
Area Engineer, AEZC-Area Office  
Arnold Air Force Station, TN 37389

Western Area Office, CE  
Vandenberg AFB, CA 93437  
416th Engineer Command 60623  
ATTN: Facilities Engineer

US Military Academy 10996  
ATTN: Facilities Engineer  
ATTN: Dept of Geography &  
Computer Science  
ATTN: DSCPER/HAEN-A

Engr. Studies Center 20315  
ATTN: Library

AMMRC, ATTN: DRXMR-WE 02172

USA ARRCOM 61299  
ATTN: DRCS-R1-1  
ATTN: DRSA-R1-1

DARCOM - Dir., Inat., & Svcs.  
ATTN: Facilities Engineer  
ARRADCOM 07801  
Aberdeen Proving Ground 21005  
Army Matls. and Mechanics Res. Ctr.  
Corpus Christi Army Depot 78419  
Harry Diamond Laboratories 20783  
Dugway Proving Ground 84022  
Jefferson Proving Ground 47250  
Fort Monmouth 07703  
Letterkenny Army Depot 17201  
Natick R&D Ctr. 01760  
New Cumberland Army Depot 17070  
Pueblo Army Depot 81001  
Red River Army Depot 75501  
Redstone Arsenal 35899  
Rock Island Arsenal 61299  
Savanna Army Depot 61074  
Sharpe Army Depot 95331  
Seneca Army Depot 14541  
Tobyhanna Army Depot 18466  
Tooele Army Depot 84074  
Watervliet Arsenal 12169  
Yuma Proving Ground 85364  
White Sands Missile Range 88002

DLA ATTN: DLA-W1 22314

FORSOM  
FORSOM Engineer, ATTN: AFEN-FE  
ATTN: Facilities Engineer  
Fort Buchanan 00934  
Fort Bragg 28307  
Fort Campbell 42223  
Fort Carson 80913  
Fort Devens 01433  
Fort Drum 13601  
Fort Hood 76544  
Fort Indiantown Gap 17003  
Fort Irwin 92311  
Fort Sam Houston 78234  
Fort Lewis 98433  
Fort McCoy 54656  
Fort McPherson 30330  
Fort George G. Meade 20755  
Fort Ord 93941  
Fort Polk 71459  
Fort Richardson 99505  
Fort Riley 66442  
Presidio of San Francisco 94129  
Fort Sheridan 60037  
Fort Stewart 31343  
Fort Wainwright 99703  
Vancouver Bks. 98660

HSC  
ATTN: HSLD-F 78234  
ATTN: Facilities Engineer  
Pittsboro AMC 00140  
Walter Reed AMC 00012

INSCOM - Ch, Inat. Div.  
ATTN: Facilities Engineer  
Arlington Hall Station (2) 22212  
Vint Hill Farm Station 22186

NDW  
ATTN: Facilities Engineer  
Cameron Station 22314  
Fort Lesley L. McNair 20319  
Fort Myer 22211

NTMC  
ATTN: NTMC-SA 20315  
ATTN: Facilities Engineer  
Oakland Army Base 94626  
Bayonne MOT 07002  
Sunny Point MOT 28461

NARADCOM, ATTN: DRDNA-F 071160

TARCOM, Pac. Div. 48090

TECOM, ATTN: DRSTE-LG-F 21005

TRADOC  
HQ, TRADOC, ATTN: ATEN-FE  
ATTN: Facilities Engineer  
Fort Belvoir 22060  
Fort Benning 31905  
Fort Bliss 79916  
Carlisle Barracks 17013  
Fort Chaffee 72902  
Fort Dix 08640  
Fort Eustis 23604  
Fort Gordon 30905  
Fort Hamilton 11252  
Fort Benjamin Harrison 46216  
Fort Jackson 29207  
Fort Knox 40121  
Fort Leavenworth 66027  
Fort Lee 23801  
Fort McClellan 36205  
Fort Monroe 23651  
Fort Rucker 36362  
Fort Still 73503  
Fort Leonard Wood 65473

TSARCOM, ATTN: STSAS-F 63120

USACC  
ATTN: Facilities Engineer  
Fort Huachuca 85613  
Fort Ritchie 21719

WESTCOM  
ATTN: Facilities Engineer  
Fort Shafter 96858

SHAPE 09055  
ATTN: Survivability Section, CCB-OPS  
Infrastructure Branch, L&NDA

HQ USEUCOM 09128  
ATTN: ECI 477-LOE  
Fort Belvoir, VA 22060  
ATTN: ATZA-DTE-EM  
ATTN: ATZA-DTE-SW  
ATTN: ATZA-FE  
ATTN: Engr. Library  
ATTN: Canadian Liaison Office (2)  
ATTN: IWR Library  
Cold Regions Research Engineering Lab 03755  
ATTN: Library

ETL, ATTN: Library 22060

Waterways Experiment Station 39144  
ATTN: Library

HQ, XVIII Airborne Corps and 28307  
Ft. Bragg  
ATTN: AFZA-FE-EE

Chanute AFB, IL 61868  
3345 CES/DE, Stop 27

Norton AFB 92409  
ATTN: AFRC-EX/DEF

Tyndall AFB, FL 32403  
AFESC/Engineering & Service Lab

NAFEC  
ATTN: RDT&E Liaison Office  
Atlantic Division 23511  
Chesapeake Division 20374  
Southern Division 29111  
Pacific Division 94860  
Northern Division 19112  
Western Division 64066  
ATTN: Sr. Tech. FAC-OST 22332  
ATTN: Asst. CDR R&D, FAC-03 22332

NCEL 93041  
ATTN: Library (Code 108A)

Defense Technical Info. Center 22314  
ATTN: DDA (12)

Engineering Societies Library 10017  
New York, NY

National Guard Bureau 20310  
Installation Division

US Government Printing Office 22304  
Receiving Section/Depository Copies (2)

# CAEADS Team Distribution

## Chief of Engineers

ATTN: DAEN-MPO-B  
ATTN: DAEN-MPR  
ATTN: DAEN-MPZ-A  
ATTN: DAEN-ZCP

## US Army Engineer District

New York 10007  
ATTN: Chief, Design Br  
Pittsburgh 15222  
ATTN: Chief, ORPCD  
ATTN: Chief, Engr Div  
Philadelphia 109106  
ATTN: Chief, NADEN-D  
Baltimore 21203  
ATTN: Chief, Engr Div  
Norfolk 23510  
ATTN: Chief, NADEN  
ATTN: Chief, NADEN-D  
Wilmington 28401  
ATTN: Chief, SAWEN-PP  
ATTN: Chief, SAWEN-PM  
ATTN: Chief, SAWCO-C  
Charleston 29402  
ATTN: Chief, Engr Div  
Savannah 31402  
ATTN: Chief, SASAS-L  
Jacksonville 32232  
ATTN: Constr. Div  
ATTN: Safety  
ATTN: Env. Res. Br.  
Mobile 36128  
ATTN: Chief, SAMEN-C  
Memphis 38103  
ATTN: Chief, Engr Div  
ATTN: Chief, LMED-D  
Vicksburg 39180  
ATTN: Chief, Engr Div  
Louisville 40201  
ATTN: Chief, Engr Div  
Detroit 48231  
ATTN: Chief, MCEED-T  
St. Paul 55101  
ATTN: Chief, CO-C  
ATTN: Chief, ED-D  
Chicago 60604  
ATTN: Chief, MCCC-C  
ATTN: Chief, MCCVE  
Rock Island 61201  
ATTN: Chief, MCRCD  
St. Louis 63101  
ATTN: Chief, ED-D  
Kansas City 64106  
ATTN: Chief, Engr Div  
Omaha 68102  
ATTN: Chief, Engr Div  
New Orleans 70160  
ATTN: Chief, LMED-DG  
Little Rock 72203  
ATTN: Chief, Engr Div  
Galveston 77550  
ATTN: Chief, SWGAS-L  
ATTN: Chief, SWGCO-C  
Albuquerque 87103  
ATTN: Chief, Engr Div  
Los Angeles 90053  
ATTN: Chief, SPLED-D  
San Francisco 94105  
ATTN: Chief, Engr Div  
Sacramento 95814  
ATTN: Chief, SPKCO-C  
ATTN: Chief, SPKED-D  
Far East 96301  
ATTN: Chief, Engr Div  
Portland 97208  
ATTN: Chief, FM-4  
ATTN: Chief, DB-6  
Seattle 98124  
ATTN: Chief, NPSCO  
ATTN: Chief, EN-DB-ST  
Walla Walla 99362  
ATTN: Chief, Engr Div  
Alaska 99501  
ATTN: Chief, NPASA-R

## US Army Engineer Division

New England 02154  
ATTN: Chief, NEDED-D  
ATTN: Chief, NEDED-T  
North Atlantic 10007  
ATTN: Chief, NADEN-A  
ATTN: Chief, NADEN-T  
Middle East (Rear) 22601  
ATTN: Chief, MEDED-T  
South Atlantic 30303  
ATTN: Laboratory  
ATTN: Chief, SADC-50  
ATTN: Chief, SADC-TA  
Huntsville 35807  
ATTN: Chief, HNEDED-CS  
ATTN: Chief, HNEDED-M  
Ohio River 45201  
ATTN: Chief, Engr Div  
North Central 60605  
ATTN: Chief, Engr Div  
Southwestern 75202  
ATTN: Chief, SWDCD-CG  
ATTN: Chief, SWDED-TA  
South Pacific 94111  
ATTN: Laboratory  
Pacific Ocean 96858  
ATTN: Chief, Engr Div  
ATTN: FM&S Branch  
ATTN: Chief, PODED-D  
North Pacific 97208  
ATTN: Chief, Engr Div

6th US Army  
ATTN: AFKC-EN

7th US Army  
ATTN: AETTM-HRD-EHD

USA ARRADCOM 07801  
ATTN: ORDAR-LCA-OK

West Point, NY 10996  
ATTN: Dept of Mechanics  
ATTN: Library

Ft. Belvoir, VA 22060  
ATTN: Learning Resources Center  
ATTN: ATSE-TD-TL (2)  
ATTN: British Liaison Officer (5)

Ft. Clayton Canal Zone 34004  
ATTN: OFAE

Ft. Leavenworth, KS 66027  
ATTN: ATZLCA-SA

Ft. Lee, VA 23801  
ATTN: DRXMC-D (2)

Ft. McPherson, GA 30330  
ATTN: AFEN-CD

Ft. Monroe, VA 23651  
ATTN: ATEN-AD (3)  
ATTN: ATEN-FE-E  
ATTN: ATEN  
ATTN: ATEN-FE-U

Aberdeen Proving Ground, MD 21005  
ATTN: AMXHE

USA-WES  
ATTN: C/Structures

Naval Facilities Engr Command  
Alexandria, VA 22332

Port Hueneme, CA 93041  
ATTN: Morell Library

Kirtland AFB, NM 87117  
AFWL/DEO

Little Rock AFB  
ATTN: 314/DEEE

Patrick AFB, FL 32925  
ATTN: XRQ

Tinker AFB, OK 73145  
2854 ABG/DEEE

Tyndall AFB, FL 32403  
AFESC/PRT

Building Research Advisory Board 20418

Dept of Transportation Library 20590

Transportation Research Board 20418

Airports and Const. Services Dir.  
Ottawa, Ontario, Canada K1A 0N8

Div of Building Research  
Ottawa, Ontario, Canada K1A 0R6

National Defense Headquarters  
Ottawa, Ontario, Canada K1A 0K2

107  
107

Spoonamore, Janet H.

CAEADS: Computer-Aided Engineering and Architectural Design System. --  
Champaign, IL : Construction Engineering Research Laboratory ; available  
from NTIS, 1982.

22 p. (Technical manuscript / Construction Engineering Research  
Laboratory ; P-133)

Presented at the 1982 Army Science Conference.

1. CAEADS. 2. Architectural design -- data processing. 3. U.S. Army --  
Military construction operations -- data processing. 1. Title. II. Series :  
Technical manuscript (Construction Engineering Research Laboratory) ; P-133.



